



CONSTRUCTION PLAN KEYED NOTES

- 1 LEASE AREA LINE, REFER TO SURVEY (IF AVAILABLE) FOR ADDITIONAL INFORMATION.
- 2 CONCRETE PAD
- 3 PRIMARY BASE TRANSCEIVER STATION. (PROVIDED BY CARRIER)
- 4 EXTENSION BTS UNITS.(PROVIDED BY CARRIER)
- 6 NEW ANTENNA SUPPORT STRUCTURE. (SEE MANUFACTURER DRAWINGS FOR DETAILS)
- 7 NEW ANTENNA SUPPORT STRUCTURE FOUNDATION - ENGINEERING PROVIDED BY OTHERS.
- 8 SITE & 2'-0" PERIMETER TO BE FILLED WITH 3" OF 1" DIA. CRUSHED ROCK ON WEED BARRIER ON 95% COMPACTED FILL.
- 9 NEW 8'-0" HIGH GALVANIZED CHAIN LINK FABRIC FENCE, 8'-0" POST TO POST TYPICAL.
- 10 10'-0" WIDE SWINGING CHAIN LINK LOCKING GATE.
- 12 PCS ANTENNAS (PROVIDED BY CARRIER).
- 13 SYSTEM DEMARCATION CABINET (BASE CONNECTION TO BTS UNITS
- 14 COAXIAL CABLING TO ANTENNAS (PROVIDED BY CARRIER). SEE RF DATA SHEET.
- 15 WAVEGUIDE ICE BRIDGE
- 17 FOR NEW TELEPHONE AND POWER TRENCH DETAIL. MAINTAIN 18" SEPARATION BETWEEN ALL POWER AND TELCO CONDUITS.
- 18 METER RACK (PROVIDED BY CONTRACTOR)

SITE NOTES

- 1. VERIFY AZIMUTHS WITH FINAL SITE CONFIGURATION SHEET FROM R.F. ENGINEER.
- 2. PROVIDE 4" CONDUIT EQUIPPED WITH 1 PULL STRING AND (2) 6 PAIR 22 GAUGE BURIED DROP WIRES . ALL TELCO CONDUITS AND TELCO WIRING MUST MAINTAIN A MINIMUM SEPARATION DISTANCE OF 18" AWAY FROM ALL A/C POWER CONDUITS AND WIRING.
- 3. PROVIDE TELECT 8 T1 DSX UNIT TO OPERATIONS FOR T1 MAINTENANCE. TELECT PART #010-5008-0001.

17 TIE INTO EXIST. TELCO & POWER SOURCE (FIELD VERIFY)

DATE: 6/17/08

DRAWN BY: DESTINY DESIGN

CHECKED BY: TC

FILE: SLO1128D NATIONAL STORAGE

REVISIONS

DATE	DESCRIPTION	INITIAL
6/17/08	ZONING DRAWING	DD

T-Mobile

121 W. Election Rd.
Suite 330
Draper, UT. 84020
(801) 816-4422
FAX (801) 816-4420

LAND DESIGN & DEVELOPMENT LLC

C/O 121 W. Election Rd.
Suite 330
Draper, UT. 84020

Destiny Design LLC

SITE NUMBER:

SLO1128D

NATIONAL STORAGE

7125 WEST 3500 SOUTH

WEST VALLEY CITY, UT

a-2