

CONSTRUCTION PLAN KEYED NOTES

- 1 LEASE AREA LINE, REFER TO SURVEY (IF AVAILABLE) FOR ADDITIONAL INFORMATION.
- 2 CONCRETE PAD
- 3 PRIMARY BASE TRANSCEIVER STATION. (PROVIDED BY CARRIER)
- 4 EXTENSION BTS UNITS.(PROVIDED BY CARRIER)
- NEW ANTENNA SUPPORT STRUCTURE. (SEE MANUFACTURER DRAWINGS FOR DETAILS)
- 7 NEW ANTENNA SUPPORT STRUCTURE FOUNDATION -ENGINEERING PROVIDED BY OTHERS.
- 8 SITE & 2'-O" PERIMETER TO BE FILLED WITH 3" OF 1" DIA.
 CRUSHED ROCK ON WEED BARRIER ON 95% COMPACTED
 FILL.
- 9 NEW 8'-0" HIGH GALVANIZED CHAIN LINK FABRIC FENCE, 8'-0" POST TO POST TYPICAL.
- 10 10'-0" WIDE SWINGING CHAIN LINK LOCKING GATE.
- 12 PCS ANTENNAS (PROVIDED BY CARRIER).
- 13 SYSTEM DEMARCATION CABINET (BASE CONNECTION TO BTS UNITS
- 14 COAXIAL CABLING TO ANTENNAS (PROVIDED BY CARRIER). SEE RF DATA SHEET.
- 15 WAVEGUIDE ICE BRIDGE
- FOR NEW TELEPHONE AND POWER TRENCH DETAIL.

 MAINTAIN 18" SEPARATION BETWEEN ALL POWER AND TELCO CONDUITS.
- 18 METER RACK (PROVIDED BY CONTRACTOR)

DATE:	6/17/08
DRAWN BY:	DESTINY DESIGN
CHECKED BY:	TC
FILE: SLO11	28D NATIONAL STORAGE

REVISIONS

DATE	DESCRIPTION	INITIAL
6/17/08	ZONING DRAWING	DD
€	尔斯 克	*







SITE NUMBER:

SL01128D

NATIONAL STORAGE 7125 WEST 3500 SOUTH WEST VALLEY CITY, UT

a-3